




**Sun Odyssey 379**

**Sun Odyssey 409**

**Sun Odyssey 439**


Certification conform with CE regulation.

	SO 379	SO 409	SO 439
<b>SPECIFICATIONS</b>			
<b>Overall length</b>	11,34 m	12,34 m	13,34 m
<b>Hull length</b>	10,98 m	11,98 m	12,99 m
<b>Waterline length</b>	10,40 m	11,00 m	12,00 m
<b>Beam</b>	3,76 m	3,99 m	4,24 m
<b>Displacement</b> light load with deep draft keel	6700 kg	7860 kg	9640 kg
<b>Standard draft</b> cast iron fin keel with elongated bulb and exterior epoxy barrier coat	1,95 m	2,10 m	2,20 m
<b>Standard keel weight</b>	1775 kg	2260 kg	2850 kg
<b>Shoal draft</b> cast iron fin keel with elongated bulb and exterior epoxy barrier coat (double rudders on SO 379)	1,50 m	1,55 m	1,60 m
<b>Shoal keel weight</b>	2039 kg	2470 kg	3150 kg
<b>Swing keel</b> epoxy coated iron keelbox with twin rudders	1,10 - 2,25 m	-	-
<b>Swing keel weight</b>	2313 kg	-	-
<b>CE category</b>	A8 / B9	A9 / B10	A10 / B11
<b>Architect / designer</b>	M. Lombard	P. Briand	P. Briand
<b>Water</b> rotomolded tank located under forward berth with deck fill	200 L	330 L	330 L
<b>Fuel</b> rotomolded tank located under aft berth with deck fill	130 L	200 L	200 L
<b>Holding tank</b> rotomolded tank located in head compartment with valve for overboard discharge via gravity and deck fitting for pump out	80 L	80 L	80 L
<b>Fridge</b> fridge compartment with vertical access	185 L	185 L	185 L
<b>SAILS</b>			
Standard mainsail horizontally-cut in high-quality dacron	■ 35 m²	■ 43,5 m²	■ 49,5 m²
Standard headsail 132% horizontally-cut in high-quality dacron	■ 35 m²	-	-
Standard headsail 106% horizontally-cut in high-quality dacron	-	■ 32,5 m²	■ 41,5 m²
Lazy bag in Sunbrella® Taupe fabric with integrated lazy jacks	■	■	■
Performance Headsail 140% in triradial cut mylar/taffeta laminate	-	□ 46,1 m²	□ 54,7 m²
Performance Headsail 132% in triradial cut mylar/taffeta laminate	□ 35 m²	-	-
Performance Headsail 106% in triradial cut mylar/taffeta laminate	-	□ 32,5 m²	□ 41,5 m²
Self-tacking jib in triradial cut mylar/taffeta laminate	□ 23,3 m²	□ 28,2 m²	□ 35,3 m²
Performance Mainsail in triradial cut mylar/taffeta laminate	□ 35 m²	□ 43,5 m²	□ 49,5 m²
Inmast furling horizontally-cut in high-quality dacron	□ 27,2 m²	□ 34,2 m²	□ 39,3 m²
Code 0 in triradial cut mylar/aramid laminate	□ 55,2 m²	□ 70 m²	□ 76,4 m²
Symmetrical spinnaker optimal size for the boat (sail not available)	99 m²	118 m²	144 m²
Asymmetrical spinnaker optimal size for the boat (sail not available)	90,4 m²	109 m²	133 m²

■ Standard □ Option - Not available

	SO 379	SO 409	SO 439
<b>SAIL HANDLING</b>			
<b>Genoa winches</b> 2 x Harken 40.2 self-tailing winches	■	-	-
<b>Genoa winches</b> 2 x Harken 46.2 self-tailing winches	-	■	■
<b>Genoa winches</b> 2 x Harken 50.2 self-tailing winches	-	□	□
<b>Coachroof winch</b> Harken 35.2 self-tailing winch to port	■	-	-
<b>Coachroof winch</b> Harken 40.2 self-tailing winches to port	-	■	■
<b>Coachroof winch</b> Harken 35.2 self-tailing winch to starboard	*	-	-
<b>Coachroof winch</b> Harken 40.2 self-tailing winches to startboard	-	*	*
<b>Harken "Rewind" electric genoa winches</b> 2 x 46.2 winches that can sheet-in and sheet-out electrically	-	□	□
<b>Electric coachroof winch</b> 1 x Harken 40.2 12v self-tailing in place of standard winch to port	-	PREFERENCE	PREFERENCE
<b>Genoa tracks</b> adjustable Harken lead cars located on coachroof	-	■	■
<b>Genoa tracks</b> adjustable Harken lead cars (located on the side decks)	■	□	□
<b>Ball-bearing track</b> for self-tacking jib	□	□	□
<b>Winch handles</b> 2 x Harken handles with ball-bearing grip	■	■	■
<b>Mainsheet and genoa sheet</b> lead back to helm station with Spinlock jammers	■	■	■
<b>Line jammers</b> Spinlock, on both sides of coachroof with return blocks	■	■	■
<b>Mainsheet traveller</b> roof-mounted traveller with ball-bearing cars, control lines lead aft to cockpit	■	■	■
<b>Spinnaker deck hardware</b> Spinlock jammers	*	*	*
<b>Asymmetrical spinnaker gear</b> halyard, 2 sheets, tack line lead forward on deck, Harken blocks	□	□	□
<b>Symmetrical spinnaker gear</b> halyard, 2 sheets, 2 guys, pole uphaul and downhaul, spinnaker pole and adjustable car for mast, Harken blocks	□	□	□
<b>MAST AND RIGGING</b>			
<b>Classic mast</b> aluminium with double spreaders	■	■	■
<b>Furling mast</b>	□	□	□
<b>Standing rigging</b> discontinuous 1x19 stainless steel wire	■	■	■
<b>Standing rigging</b> discontinuous Dyform® stainless steel wire	▲	▲	▲
<b>Backstay</b> double	■	■	■
<b>Backstay</b> adjustable via mechanical adjuster	□	□	□
<b>Genoa furler</b> with double slot, attachment to stemhead fitting and furling line lead aft to port helm winch	■	■	■
<b>Running rigging</b> polyester topping lift, mainsail halyard, genoa halyard, mainsheet, genoa sheets	■	■	■
<b>Running rigging</b> Dyneema® mainsail halyard, genoa halyard, mainsheet, genoa sheets	▲	▲	▲
<b>Rigid boom vang</b> with gas cylinder and control line lead aft to the cockpit	*	*	■
<b>COCKPIT</b>			
<b>Wood inlay</b> on cockpit bench seating	■	■	■
<b>Wood cockpit</b> floor inlay	□	□	□
<b>Wood side decks</b> hand-laid wooden side decks	□	□	□
<b>Cockpit lockers</b> 1 locker under bench seat and 1 lazarette locker under the port helm seat	■	-	-
<b>Cockpit lockers</b> 2 lockers under bench seats and 1 lazarette locker under the port helm seat for technical access to steering system	-	■	■
<b>Liferaft locker</b> located in dedicated compartment between helm seats	90x59x34 cm	90x55x34 cm	90x54x34 cm
<b>Storage compartment for companionway door</b> in forward section of liferaft locker	-	■	■
<b>Storage compartment for companionway door</b> in cockpit locker	■	-	-
<b>Line lockers</b> under helm seats for lines from the primary winches, location for deck fills, cockpit speakers and shorepower inlet	-	■	■
<b>Fold down swim platform</b> with telescopic swim ladder	■	■	■
<b>Cockpit table</b> folding table with storage, cup holders, stainless steel handrail, courtesy lighting, 12v plug	PREFERENCE	■	■
<b>Solid wood cockpit table</b> with all the same functions of the standard table, but with wooden leaves	□	□	□
<b>Gas locker</b> located in lazarette locker under starboard helm seat, room for 2 gas bottles with connection to gas system and cut-off valve under stove in the galley	■	■	■
<b>Wheels</b> 2 leather-covered steering wheels with compasses at each steering position and stainless steel grabrails	■	■	■
<b>Black, composite steering wheels</b>	□	□	□
<b>Emergency tiller</b> delivered with the boat, chrome fitting in cockpit floor	■	■	■
<b>Steering wheel covers</b> Sunbrella® Taupe with zips for easy removal	□	□	□
<b>Cockpit table cover</b> Sunbrella® Taupe (with or without GPS)	□	□	□
<b>Instrumentation</b> dedicated space for instruments within easy reach of helm positions, room for GPS chartplotter mounted at aft end of cockpit table with easy viewing from each helm	■	■	■
<b>Engine controls</b> throttle and engine control panel mounted at starboard helm, engine panel includes, RPM gauge, warning lights, ignition	■	■	■
<b>Cockpit shower</b> retractable hot and cold water shower with tap	PREFERENCE	PREMIERE	■
<b>Cockpit cushions</b> Sunbrella® Taupe cushions for seating area with attachment clips	□	□	□
<b>Cockpit bimini</b> Sunbrella® Taupe with stainless steel bows, retractable with storage cover	□	□	□
<b>Cockpit sprayhood</b> wide Sunbrella® Taupe with vinyl windscreen with zip-out middle window for ventilation, retractable	□	□	□
<b>DECK HARDWARE</b>			
<b>Anchor locker</b> room for anchor and tackle, integrated windlass area, holder for windlass handle	■	■	■
<b>Bow pulpit</b> open, stainless steel	■	■	■
<b>Stern pulpits</b> stainless steel with flag holder, buoy bracket	■	■	■
<b>Outboard engine bracket</b> mounted on stern pulpit	□	□	□
<b>Electric windlass</b> Quick 1000W combination rope and chain, vertical-mounted in the anchor locker, hand-held remote, manual handle	□	PREMIERE	■
<b>Windlass control</b> second windlass control mounted in cockpit with chain counter for easy, short-handed anchoring	-	□	□
<b>Anchor roller</b> single stainless steel fitting	■	■	■
<b>Anchor roller</b> double stainless steel fitting with tack point reinforcement	PREMIERE	PREMIERE	PREMIERE
<b>Anchoring kit</b> Delta anchor 16kg with 28 meters of 10mm chain and 40 meters of 18mm line	□	-	-
<b>Anchoring kit</b> Delta anchor 20kg with 32 meters of 10mm chain and 45 meters of 18mm line	-	□	□
<b>Lifelines</b> double level of stainless steel lifelines, stainless steel stanchions	■	■	■
<b>Lifeline gates</b> opening gates on each side	PREFERENCE	PREFERENCE	PREFERENCE
<b>Toerail</b> and drainage for side deck	■	■	■
<b>Wood rubrail</b> for hull protection	□	□	□
<b>Cleats</b> 4 x stainless steel mooring cleats forward and aft	■	■	■
<b>Midship cleats</b> 2 x stainless steel cleats placed on side deck	PREMIERE	PREMIERE	PREMIERE
<b>Mooring kit</b> fenders and docklines	□	□	□
<b>Handrails</b> sculpted, long wood handrails on coachroof for secure movement forward	■	■	■

▲ Performance package \* Navigation package ■ Standard □ Option - Not available

	SO 379	SO 409	SO 439
<b>TECHNICAL FEATURES AND OPTIONS</b>			
<b>CONSTRUCTION</b>			
<b>Deck</b> Prisma Process® injected deck, ISO gelcoat surface, discontinuous balsa block coring	■	■	■
<b>Hull</b> solid, hand-laid fibreglass, ISO gelcoat surface, protective barrier coat	■	■	■
<b>Structure</b> inner fibreglass grid, high-load zones cut out, drainage system through structure	■	-	-
<b>Structure</b> 3 <sup>rd</sup> generation inner fibreglass grid, high-load zones cut out and relaminated, drainage system through structure, special emergency repair zone in keel area	-	■	■
<b>LIGHTING</b>			
LED navigation lights and anchor light	PREMIERE	PREMIERE	PREMIERE
Flush mounted LED chromed brass ceiling lights in saloon, head compartments and cabins	■	■	■
Leather-wrapped LED reading lights in forward cabin and aft cabin (s)	■	■	■
Indirect lighting under side decks in saloon and head compartments	■	■	■
Indirect LED lighting under furniture in saloon	-	PREFERENCE	PREFERENCE
Gooseneck chart light mounted at nav station	■	■	■
<b>ELECTRICAL</b>			
12 v alternator output	80 A	80 A	80 A
Charge distributor/isolator	■	■	■
Engine start battery capacity, batteries located under aft berths	70 Ah	110 Ah	110 Ah
Domestic battery bank capacity, batteries located under aft berths	70 Ah	220 Ah	220 Ah
Extra 70 Ah domestic battery	PREMIERE	-	-
2 x Extra 110 Ah domestic battery	-	PREMIERE	PREMIERE
Positive battery switch for engine and domestic bank and general cut-off switch mounted on panel in aft cabin	■	■	■
Shorepower 220 v inlet with differential breaker, one 220v plug per cabin, 220v plug in galley, saloon and nav station	PREMIERE	PREMIERE	■
40 A battery charger, multi-phase	PREMIERE	-	-
60 A battery charger, multi-phase	-	PREMIERE	PREMIERE
Inverter 2000 W12v/220v	-	-	□
Electrical panel with 12v breakers, 220v breakers, 12v ammeter, 12v consumption meter, 12v charging meter	■	■	■
<b>Solar panels</b> on coachroof 2 x 45W with charging relay	□	□	□
12 v plug per cabin and at nav station	■	■	■
220 v stainless steel microwave, installed in galley cabinet	□	□	□
<b>PLUMBING</b>			
Hot and cold pressurised water distributed through-out the boat via semi-rigid hose	■	■	■
"Heavy-duty" water pump and accumulator tank for consistent water pressure	■	■	■
40 litre hot water tank that is connected to engine heat exchanger and to 230 v electrical system	■	■	■
Chromed shower faucets in washrooms	■	■	■
Electric bilge pump on float switch and manual dual-action pump in the cockpit	■	■	■
Extra fresh water tank 130L located under aft starboard berth	□	-	-
Extra fresh water tank 200L located under aft starboard berth	-	□	PREMIERE
Digital water level display	■	■	■
Shower sumps equipped with individual electric pumps with filters and on-off switches	■	■	■
Large manual pump marine toilets	■	■	■
Electric Quiet-Flush toilets in place of standard, available for each head compartment	-	□	□
80 litre holding tank with gravity drain and deck fitting for forward starboard head (port aft head equipped with standard 80L tank)	-	□	□
<b>ENGINE AND STEERING</b>			
Yanmar 3YM30 <b>29 HP</b> , 21Kw <b>Sail drive</b>	■	-	-
Yanmar 3JH5-CE <b>40 HP</b> , 29.4 Kw <b>Sail Drive</b>	-	■	-
Yanmar 4JH5-CE <b>54 HP</b> , 39.6 Kw <b>Sail Drive</b>	-	-	■
Compatible 360 Docking	-	■ <b>POD 60</b>	■ <b>POD 90</b>
Fully soundproofed engine compartment with engine access behind stairwell and from aft cabin	■	■	■
Fuel / water separator	■	■	■
Built-in muffler, forced air ventilation and stainless steel exhaust fitting aft	■	■	■
Fixed 3-blade propeller	■	■	■
Folding propeller, 3-blade, Flex-o-Fold	▲	▲	▲
Bow thruster 4.3hp/3.2kw installed in a tunnel with dedicated batteries	□	-	-
Bow thruster 9.5hp/7.1kw installed in a tunnel with dedicated batteries	-	□	□
Fibreglass rudder	■	■	■
<b>COMFORT FEATURES AND OPTIONS</b>			
<b>Fixed hull ports</b> with shades	4	8	8
<b>Opening cockpit and roof ports</b>	2	2	2
<b>Lateral fixed windows</b>	6	6	6
<b>Opening ports integrated into lateral windows</b>	2	2	2
<b>Opening deck hatches</b>	4	6	7
<b>Combination shade/insect screens</b> for deck hatches	PREMIERE	PREMIERE	PREMIERE
<b>Simrad audio docking station SonicHub</b> with remote	PREFERENCE	PREFERENCE	PREMIERE
<b>BOSE® 2.1 speaker system</b> ACCOUSTIMASS 3, speakers with base unit in saloon	-	-	PREMIERE
<b>Saloon stereo speakers</b> x 2	PREFERENCE	PREFERENCE	-
<b>Cockpit speakers</b> x 2, watertight	PREFERENCE	PREFERENCE	PREMIERE
<b>LED TV 22"</b> mounted on an articulating arm on main saloon bulkhead to port of the forward cabin doorway and DVD player	-	□	□
<b>Amplified antenna for TV</b> for masthead mounting	-	□	□
<b>Air Conditioning</b> 220v 16000 BTU 1 unit installed under saloon seating, vents in saloon, forward and aft cabins control panel and thermostat (for 2 cabin version only)	□	-	-
<b>Air Conditioning</b> 220 v 24000 BTU 2 units installed under saloon seating and in stern, vents in saloon, head compartments and forward and aft cabins control panel and thermostat	-	□	-
<b>Air Conditioning</b> 220 v 32000 BTU 1 unit installed in the stern, 1 unit installed in the saloon and 1 unit installed in the forward cabin, vents in saloon, head compartments and forward and aft cabins control panel and thermostat	-	-	□
<b>Forced air heating</b> 1 unit 5500 BTU Webasto® diesel heater installed in stern, vents in aft cabin, saloon and head compartments	□	□	□
<b>Forced air heating</b> 1 unit 5500 BTU + 1 unit 2000 BTU Webasto® diesel heater installed in stern, vents in aft cabin, saloon and head compartments (only for the 4 cabins version)	-	-	□

▲ Performance package \* Navigation package ■ Standard □ Option - Not available

	SO 379		SO 409				SO 439	
	2C1/H	3C1/H	2C1/H	3C1/H	3C2/H	2C2/H	3C2/H	4C2/H
INTERIOR FEATURES AND OPTIONS								
WOOD								
Fine Teak® interior	laminated panels with solid wood trim around galley, companionway and cabinetry, finished in satin UV stabilised varnish	■	■	■	■	■	■	■
Laminate floorboards	with light-coloured lines, varnished edges	■	■	■	■	■	■	■
Laminate floorboards	in an oak finish, varnished edges	□	□	□	□	□	□	□
FORWARD CABIN								
Forward owner's cabin	with central berth and storage forward of the berth	■	■	■	■	■	■	-
Double berth,	with wood trim, high-density foam mattress	2,07 x 1,85 m	2,07 x 1,85 m	2,10 x 2,00 m	2,10 x 2,00 m	2,10 x 2,00 m	2,14 x 2,00 m	-
Deep cabinet	with shelves and hanging rod	2	2	2	2	1	1	-
White vinyl lining	on hull with lateral wood shelf	■	■	■	■	■	■	-
Desk/vanity	with leatherette lining and fold-up mirror, reading light and chair with backrest	-	-	□	□	-	-	■
Private forward head compartment	with sink, clothes hook, mirror, towel holder, toilet paper holder, cabinet above sink and electric drainage pump	-	-	-	-	■	■	-
Plexiglass folding door	for separate shower compartment	-	-	-	-	-	PREMIERE	-
Double forward cabins	with 2 single bunk berths and forward V-berth	-	-	-	-	-	-	■
Double berth	with wood trim, high-density foam mattress	-	-	-	-	-	-	2,14 x 2,00 m
Twin single bunks	in separate cabin with storage locker	-	-	-	-	-	-	2,11 x 0,70 m
Deep cabinet	with shelves and hanging rod	-	-	-	-	-	-	■
White vinyl lining	on hull with lateral wood shelf	-	-	-	-	-	-	■
Forward head compartment	with sink, clothes hook, mirror, towel holder, toilet paper holder, cabinet above sink and electric drainage pump	-	-	-	-	-	-	■
Plexiglass folding door	for separate shower compartment	-	-	-	-	-	-	PREMIERE
AFT CABIN								
Aft owner's cabin	with access to starboard and large berth	■	-	■	-	-	■	-
Double berth	with high-density foam mattress	2,02 m x 1,94 m	-	2,00 m x 1,78 m	-	-	2,00 m x 1,78 m	-
Deep cabinet	with shelves and hanging rod	■	-	■	-	-	■	-
White vinyl lining	on hull with lateral wood shelf	■	-	■	-	-	■	-
Large head compartment aft	with sink, clothes hook, mirror, towel holder, toilet paper holder, cabinet above sink and electric drainage pump	■	-	■	-	-	■	-
Plexiglass folding door	for separate shower compartment	PREMIERE	-	PREMIERE	-	-	PREMIERE	-
Locker and technical compartment	with access through head compartment, storage baskets, lighting and lots of extra space for storage under the exterior cockpit locker	■	-	■	-	-	■	-
Twin aft cabins		-	■	-	■	-	■	■
Double berths,	high-density foam	-	2,02 m x 1,58 m	-	2,00 m x 1,57 m	2,00 m x 1,57 m	-	2,00 m x 1,60 m
Deep cabinet	with shelves and hanging rod per cabin	-	■	-	■	■	-	■
White vinyl lining	on hull with lateral wood shelf	-	■	-	■	■	-	■
Head compartment aft	with sink, separate shower, clothes hook, mirror, towel holder, toilet paper holder, cabinet above sink, electric drainage pump, access from saloon	-	■	-	■	■	-	■
Plexiglass folding door	for separate shower compartment	-	PREMIERE	-	PREMIERE	PREMIERE	-	PREMIERE
NAVIGATION STATION								
Navigation station	full-function with general electrical panel, room for the latest in GPS chartplotters and bookshelf	■	■	■	■	■	■	■
Central nav desk	with leatherette lining and interior storage	-	-	■	■	■	■	■
Hanging locker		■	-	-	-	-	-	-
SALOON								
Saloon	with U-shaped seating area to starboard, wrap-around cushions and storage under seating area	■	■	■	■	■	■	■
Saloon dining table	with wood fiddles, removable pedestal legs	■	■	■	■	■	■	■
Luxury saloon table	with folding leaves and central bar cabinet	□	□	-	-	-	-	-
Luxury salon table	with central bar unit, folding top, and sliding tracks to transform into double berth	-	-	PREFERENCE	PREFERENCE	PREFERENCE	PREFERENCE	PREFERENCE
Saloon berth conversion kit		□	□	□	□	□	□	□
Storage cabinets	along hull sides	■	■	■	■	■	■	■
Lounge seating	to port with plush cushions and upper storage cabinets	■	■	■	■	■	■	■
2 removable stools	for saloon with tie-down kit	-	-	□	□	□	□	□
Companionway	with wood steps and non-slip strips	■	■	■	■	■	■	■
Plexiglass companionway door	with dedicated storage location	■	■	■	■	■	■	■
GALLEY								
Galley	with double stainless steel sinks with covers, solid countertops, chrome plumbing fittings, storage cabinets and drawers	■	■	■	■	■	■	■
L-galley	to port with glass separator between galley counter and seating area	■	■	■	■	■	■	■
Storage compartment	for books and magazines built into the galley façade	■	■	■	■	■	■	■
Gimballed 2-burner stove	with oven with stainless steel protection bar	■	■	■	■	■	■	■
Luxury 2-burner stove	with black finish, wood handle, stainless steel oven/broiler	PREMIERE	PREMIERE	PREMIERE	PREMIERE	PREMIERE	PREMIERE	PREMIERE
Single fridge box	with freezer area, wire baskets, 12v refrigeration and integrated compressor	■	■	■	■	■	■	■
HEAD ROOM								
Forward cabin		1,80 / 1,84 m		1,84 m			1,88 m	
Aft cabin (s)		1,90 m		1,95 m			1,97 m	
Companionway		1,93 m		1,94 m			1,97 m	
Saloon		1,81 / 1,92 m		1,92 m			1,96 m	
Galley		1,88 m		1,91 m			1,95 m	



JEANNEAU

Ets JEANNEAU - BP 529 - 85505 LES HERBIERS CEDEX - FRANCE - TEL +33 (0)2 51 64 20 20 - FAX +33 (0)2 51 67 37 65

INTERNET : <http://www.jeanneau.com>

■ Standard □ Option - Not available C = Cabins H = Head

